

227 4894
CH12752 HW:NA

23rd February, 1987.

Dear Sir,

Re: Franna 10 Tonne Mobile Crane Model 4WD10

In reply to your letters dated 23rd December, 1986 and 15th January, 1987 relative to the above, I advise that your drawings numbered 1760 Rev 2, 1751 Rev 2, 1762 Rev 2, 1763 Rev 2, 1764 Rev 2, 1765 Rev 2, 1766 Rev 2, M-6-01 and M-6-02 have been checked.

Design

The design of the crane is hereby approved for maximum safe working loads as per manufacturers load chart DWG No. Q148 when operating on hard level ground.

The design of this crane is subject to any alteration or modification shall not be covered by this design approval. A new submission regarding such alteration or modification shall be presented to the Chief Inspector for approval.

Construction

Cranes constructed in accordance with this design will be acceptable for use in Queensland subject to:-

1. Construction being to the requirements of S.A.A. Code AS1418.
2. Power lowering being provided with deadman control and a lock out device to prevent free fall of the load where a free fall facility is provided.
3. Marking being to the requirements of the relevant Australian Standard Code.
4. A copy of the approved load chart being displayed in the cabin of the crane.

A Certificate of Inspection with respect to each unit will be issued on completion of overload and stability testing. The requisition loading during abovementioned tests will be the maximum rated load plus 10% for overload test and plus 25% for stability test.

Such testing and inspection shall be to the satisfaction of an Inspector of Machinery of this Division.

To arrange inspection and testing phone 227 5304.

B/c Senior Inspector of Machinery
NORTHSIDE

For your information.

Mr. B.L. Hain,
Franna Cranes Pty Ltd.,
165 Lavarack Avenue,
EAGLE FARM. Q. 4007.

CHIEF INSPECTOR

23.2.87

.../2